



**TUALATIN HILLS**  
**PARK & RECREATION DISTRICT**

**Tualatin Hills Park & Recreation District**  
**Signage Master Plan**

April 2009  
Revised January 2014

---

# **Tualatin Hills Park & Recreation District Signage Master Plan**

**April 2009**

**Revised January 2014**

## **With Participation and Support from the Tualatin Hills Park & Recreation District Board of Directors**

Joseph Blowers

John Griffiths

Jerry Jones

Larry Pelatt

Bob Scott

## **ORIGINAL PROJECT CONSULTANT**

Designwest, Jason West, Principal and Creative Director, Team Leader

Bill Dean, Sign Fabrication Consultant

## **SIGNAGE MASTER PLAN TEAM**

Park District Staff

Steve Gulgren, ASLA, Superintendent of Planning and Development

Rene' Brucker, Project Manager

## **MANAGEMENT TEAM**

Doug Menke, General Manager

Keith Hobson, Director of Business and Facilities

Jim McElhinny, Director of Park & Recreational Services

Hal Bergsma, Director of Planning

Aisha Willits, Deputy Director of Planning

Bob Wayt, Director of Communications and Outreach

Geoff Roach, Director of Community Partnerships

Jessica Collins, Executive Secretary

---

## **ACKNOWLEDGEMENTS**

The project team acknowledges the invaluable contributions of the following individuals and groups in preparing this plan:

### **THE SIGNAGE MASTER PLAN PROJECT TEAM**

Bruce Barbarasch, Superintendent of Natural Resources and Trails Management

Lindsay Beckman, Office Tech

Tim Bonnin, Park Planner

Rene' Brucker, Park Planner

Scott Brucker, Superintendent of Sports

Jerry Burgess, Maintenance Operations

Dave Chrisman, Superintendent of Maintenance Operations

Steve Gulgren, Superintendent of Planning and Development

Mark Hokkanen, Risk and Contract Manager

Mike Janin, Superintendent of Security Operations

Sue LeBlanc, Graphics Specialist

Lisa Novak, Superintendent of Special Programs and Special Activities

Eric Owens, Superintendent of Recreation

Nicole Paulsen, Planning & Development Coordinator

Julie Rocha, Athletic Center Supervisor

Bob Wayt, Director of Communications and Outreach

### **ADVISORY COMMITTEES**

Cedar Hills Recreation Center Advisory Committee

Conestoga Recreation Center Advisory Committee

Garden Home Recreation Center Advisory Committee

Jenkins Estate Advisory Committee

Trails Advisory Committee

---

# Executive Summary

## Purpose of Document

The Tualatin Hills Park & Recreation District's (Park District) Signage Master Plan (SMP) is a guide for all future exterior signs in the Park District's system of parks, trails, recreation centers and natural areas. The Signage Master Plan includes graphic design standards for the variety of sign types necessary for the various conditions found throughout the District.

Signs located at, or on public outdoor facilities perform the integral function of connecting a site and its visitors. They can identify, direct and interpret features within a park site and provide the users with a sense of knowledge and safety. Signs also identify the location as a Tualatin Hills Park & Recreation District site, which evokes images of highly maintained facilities and excellent public service.

In order for any signage system to be effective, it must have unity in both its message and basic design. Unity of message enables visitors to gain an understanding of appropriate park use and appreciation of the diverse resources owned and managed by the Tualatin Hills Park & Recreation District. Unity of basic sign design identifies different sites as part of a larger park system and enables visitors to locate and access those parks with minimal effort.

This document provides guidelines for planning and implementing a signage system that promotes a positive relationship between the general public and the Tualatin Hills Park & Recreation District. Signage within the District provides image and identity for the District, identifies names and locations of individual parks, trails, natural areas and facilities, orients visitors to individual sites and the resources provided therein, provides visitors with regulatory information, assists visitors with wayfinding within individual sites, provides visitors with interpretive information regarding significant topics of natural area restoration, exhibits, landscape features, historical or cultural sites, flora and fauna, and other District programs, and provides visitors with emergency information, warnings and other safety issues.

In addition to the Signage Master Plan, a Wayfinding Plan for the Howard M. Terpenning (HMT) Recreation Complex has been developed to provide patrons the necessary site signage to make their experience navigating the complex trouble free.

## Master Plan Process

On February 5, 2008 the District's Project Design Team met to discuss and gather information relating to existing signage, concerns, requests, and observations. This information was used to help develop the project scope and was included in the project's Request for Proposals (RFP). In June 2008, Park District staff hired a graphic design consultant, Designwest, to embark on the process of creating and establishing exterior signage design standards. The process began with the Park District's project design team touring numerous sites with Designwest to introduce our consultant's team to the existing signage at a variety of District parks, trails and facilities. Team members were able to provide

---

background information in regards to signage, maintenance, location concerns, and overall signage needs. The tour provided our consultant with a clear understanding of the District's need to create visually unified signage, improve sign management, utilize sustainable materials and international Park & Recreation symbols, and minimize sign maintenance requirements.

Project Team meetings were conducted to determine the hierarchy of sign types to be developed for the signage classification system. Once determined, our consultant developed signage design concepts for each sign type within each sign family (site signs and trail signs). Staff, management and selected Advisory Committees reviewed and discussed the various sign options, coming to consensus on one option to recommend to the Board of Directors. Upon Board acceptance of the recommended design concept, Designwest proceeded to refine all the sign types for all of the signage classifications, incorporating the Project Teams' comments and fine-tuning the content of each sign.

The HMT Recreation Complex Wayfinding Plan incorporates the sign types found in the Signage Master Plan. The Plan utilizes a hierarchy of Site Identification Signs at the numerous entrances to the complex. Directional Signs for interior navigating to the various parking areas, activities and facilities and Field Identification Signs for ease of locating each field. Kiosks are located in key areas for the posting of maps, park rules, educational material, and upcoming THPRD events. The HMT Recreation Complex Wayfinding Plan is designed to help vehicular traffic and pedestrians navigate the complex effortlessly.

The draft Signage Master Plan (graphics and text) and the HMT Recreation Complex Wayfinding Plan were presented to the Board of Directors at the April 6, 2009 Board of Directors meeting for review and approval.

### **Goals of the Signage Master Plan:**

#### **Goal #1: Understanding District Needs**

##### Objectives:

- Assess existing conditions
- Assess maintenance needs
- Gather input and assess and analyze the needs of parks, trails, natural resources and facilities across the District
- Review County and City signage code requirements

---

**Goal #2: Develop visually uniform sign designs that are cohesive with the various sign types used throughout the District.**

Objectives:

- Create a signage classification system (sign types)
- Create graphic design standards and specifications per sign types
- Consider sign locations and installation techniques
- Minimize sign maintenance requirements
- Improve sign management
- Emphasize use of sustainable materials
- Utilize international Park & Recreational symbols (pictograms)

**Goal #3: Develop a Signage Master Plan and HMT Wayfinding Plan**

Objectives:

- Combine the signage classification system, graphic design standards and specifications in a manual form for use by all District Departments and Facilities
- Utilize the Signage Master Plan in the development of the HMT Wayfinding Plan
- Seek Board approval for the Signage Master Plan and HMT Wayfinding Plan
- Analyze the cost / benefit of an in-house vinyl sign machine

### **Update**

In November 2013, a new THPRD logo was rolled out. A Signage Master Plan project team met to discuss any other changes that needed to be made to the plan. During implementation of the original plan, the planning and maintenance departments found a better way to install the signs and suggestions were made to improve the design of the signs to enhance visual appeal. Some new signs were added, redundant signs were removed, some dimensions were changed, and the way the signs are made has changed. With these changes in the Signage Master Plan, the District will continue to evoke images of highly maintained facilities and excellent public service.

Acknowledgements	i–ii
Executive Summary	ii–v
Table of Contents	vi
Sign Type Index	vii
Sign Type Drawings	A.1 – U.3
Typefaces	X.1
Colors	X.2
THPRD Logo	X.3
Symbols	X.4 – X.6
Sign Installation Information	X.7
Sign Post Assembly	X.8–X.11
Anti-Graffiti Products	X.12
Sign Codes	X.14
Safety Signs	Appendix A

---

All designs, plans and drawings contained herein must be reviewed by the Owner and any of the Owner's chosen architects and engineers in connection with the execution of all required construction documentation and code conformance in respect to this project. No services rendered by the designer shall be deemed to constitute the designer as an engineer or architect.

Due to the wide variety of interpretations regarding compliance with the ADA law, please note that no warranty is either expressed or implied and Designwest cannot assume liability for errors, omissions or any damages (whether direct, indirect, consequential or incidental) resulting from the use or interpretation of this material.

These documents have been created solely for the use of the owner in connection with this project and shall not be used on any other projects by any other person without written consent of THPRD. These documents contain copyrighted proprietary original work and are not to be used or duplicated by anyone outside of Tualatin Hills Park & Recreation District without written permission.

**SIGN TYPES**

IDENTIFICATION SIGNS

- A. Identification Signs
  - A1. Standard Site Identification
  - A2. Large Site Identification
  - A3. Small Site Identification
  - A4. Major Site Identification
  
- B. Building Identification Signs
  - B1. Building Identification Letters
  - B2. Building Identification Panel
  - B3. Building Identification Small
  
- C. Room & Area Identification Signs
  - C1. Restroom (Women)
  - C2. Restroom (Men)
  - C3. Restroom (Unisex)
  - C4. Area Identification Flag
  - C5. Area Identification Overhead
  - C6. Area Identification Letters
  - C7. Parking Area Identification
  - C8. Area Identification Symbols
  - C9. Small Area Identification
  
- D. Trailhead Signs
  - D1. Trailhead Identification (Small)
  - D2. Trailhead with Map
  
- E. Field Identification Signs
  - E1. Field Identification
  - E2. Court Identification (Tennis)
  - E3. Field Identification (Ball Field)
  - E4. Field Identification (Multi-Sport)

INFORMATION SIGNS

- F. Information Signs
  - F1. Field Use By Permit
  - F2. Field Maintenance
  - F3. Do Not Feed Wildlife
  - F4. Restroom Location
  - F5. Restroom Location w/Map
  - F6. No Smoking
  
- H1. Site Map
  
- K1. Kiosk

TEMPORARY SIGNS

- L1. Area Closed
- L2. Field Closed
- L3. Trail Closed
  
- M. Seasonal & Events

REGULATORY SIGNS

- R. Regulatory Signs
  - R1. Park/Trail Rules
  - R2. Disc Golf Rules
  - R3. Play Area Rules
  - R4. Dog Park Rules
  - R5. Basketball Rules
  - R6. Hockey Rules
  - R7. Skate Park Rules
  - R8. Tennis Rules
  - R9. Synthetic Field Rules
  - R10. BMX Track Rules
  - R11. Community Garden Rules

SAFETY SIGNS


- S. Safety & Warning Signs
  - S1. Walk Bicycles

DIRECTIONAL & TRAFFIC SIGNS

- T. Directional & Traffic Signs
  - T1. Trail Directional
  - T2. Trail Mile Marker
  - T3. Trail Connection
  - T4. Trail Crossing
  - T5. Pedestrian Directional
  - T6. Wall Directional
  - T7. Parking Lot Directional
  - T8. Vehicle Directional
  - T9. Vehicle A-board

UNIQUE SIGNS

- U. Unique & Special Signs



**Sign Type A1 - Standard Site Identification**

52.5" w x 28" h, .125" thick aluminum panel - 1/2" corner radius, double-sided with matte digital print vinyl and 3M Vandal Resist, fastened to 3.5" square structural plastic lumber posts.

Panel colors: 1, 3 satin finish.

Logo: 35" wide, colors 5, 6, 7, 8, 9.


Park Name Text: 3.25" cap. ht. applied vinyl, Arial Bold, color 1.

Secondary Text: 1.5" cap. ht. applied vinyl, Arial Regular, color 1.

Pictograms: 4" applied vinyl, color 1.


**Sign Type A1 - Standard Site Identification**

52.5" w x 28" h



**POST ENLARGEMENT 'A-A' SECTION**

SCALE: 1" = 3"





**Sign Type A2 - Large Site Identification**

71.5" w x 36" h - 1/2" corner radius, aluminum panel, double-sided with matte digital print vinyl and 3M Vandal resist, fastened to two 3.5" square structural plastic lumber posts.

Panel colors: 1, 3 satin finish.


Logo colors 5, 6, 7, 8, 9.

Park Name Text: 5" cap. ht. Arial Bold, color 1.


Pictograms: 6" applied vinyl, color 1.

Note: code requires use of either the tall or short version of Type A2. Signs above 48" tall must have a clearance between grade and the bottom of the message panel of at least 24".





1 Elevation - Sign Type A3  
A3.1



2 Post Detail- Sign Type A3  
A3.1

**Sign Type A3 - Small Site Identification**

12" w x 7.5" h, 1/8" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to one (1) 2" x 2" galvanized steel utility post with tamper-resistant hardware (paint to match).

Panel color: 3, satin finish. Text on one side, paint back and sides of panel.

Text: 1" cap. ht., Arial Bold, 3/4" cap. ht. Arial Regular, color 1.

Post Height: 72".

Note: typically installed above Sign Type R1 on the same post.



1  
A3.2 Layout Detail - Sign Type A3



1 Elevation - Sign Type A4  
A4.1

**Sign Type A4 - Major Site Identification**

52" w x 60" h, 3/8" thick aluminum panel with applied vinyl, double-sided, with matte digital print vinyl and 3M Vandal resist, fastened to 6" x 6" powder-coated metal posts with tamper-resistant hardware.


Panel colors: 1, 3.

Logo: colors 5, 6, 7, 8, 9.

Park Name Text: 5¼" cap. ht., Arial Bold, color 1.

Secondary Text: 3¼" cap. ht. Arial Regular, color 1.

Pictograms: 5", color 1.



1 Detail - Sign Type A4  
A4.2



1 Elevation - Sign Type B1  
B1.1 Administration Building Facade



**GARDEN HOME  
RECREATION CENTER**



**CONESTOGA  
RECREATION & AQUATIC CENTER**



**BEAVERTON  
SWIM CENTER**

2 Elevation - Sign Type B1  
B1.1 THPRD Facilities

**Sign Type B1 - Building Identification**

Logo: .25" thick aluminum, matte vinyl logo with 3M Vandal Resist.

3-12" high dimensional plastic letters, color 4 (or Navy Blue).

Note: Size varies depending on location and space available. Thickness of letters varies with letter height.

12" high = 1" thick

6" high = 3/4" thick

3" high = 1/2" thick



1 Elevation - Sign Type B2  
B2.1

#### Sign Type B2 - Building Identification Panel

48" w x 24 h, .125" thick aluminum panel, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall with tamper-resistant hardware.

Panel colors: 1, 3, satin finish.

Screened Logo: 7.5" wide, colors 5, 6, 7, 8, 9.

THPRD Screened Text: 1.75" cap. ht., Arial Bold, color 7.

Building Name Text: 3.5" cap. ht., Arial Bold, color 1.

Secondary Text: 2.5" cap. ht., Arial Regular, color 1.



1 Elevation - Sign Type B3  
 B3.1 Horizontal



1 Elevation - Sign Type B3  
 B3.2 Vertical


**Sign Type B3 - Building Identification Small**

.125" thick aluminum panel, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall with tamper-resistant hardware. Both horizontal and vertical versions.

Panel colors: 1, 3, satin finish.

Colors 5, 6, 7, 8, 9.

Text: Arial Bold



**Sign Type C1 - Restroom (Women)**

6"w x 8.5" h painted exterior grade ADA sign panel, etched aluminum - 1/2" corner radius, .125" thick with tactile and braille message.

**Background:** color 3, satin finish.


**Tactile Message:** 5/8" cap. height, center text on sign, color 1.

**Pictogram:** color 1.

**Paint braille to match background.**

**Note:** for facilities where not all restrooms are ADA compliant, accessible restrooms must be identified with the access symbol. See page X.7.

Typically installed with VHB tape and silicone.



**Sign Type C2 - Restroom (Men)**

6" w x 8.5" h painted exterior grade ADA sign panel, etched aluminum, 1/2" corner radius, .125" thick with tactile and braille message.

Background: color 3, satin finish.


Tactile Message: 5/8" cap. height, center text on sign, color 1.

Pictogram: color 1.

Paint braille to match background.

Note: for facilities where not all restrooms are ADA compliant, accessible restrooms must be identified with the access symbol. See page X.7.

Typically installed with VHB tape and silicone.



1 Elevation - Sign Type C3  
C3.1 Half full scale

2 Section - Sign Type C3  
C3.1 Half full scale

**Sign Type C3 - Restroom (Unisex)**

6" w x 8.5" h painted exterior grade ADA sign panel, etched aluminum, .125" thick, 1/2" corner radius, with tactile and braille message.

Background: color 3, satin finish.


Tactile Message: 5/8" cap. height, center text on sign, color 1.

Pictogram: color 1.

Paint braille to match background.

Note: for facilities where not all restrooms are ADA compliant, accessible restrooms must be identified with the access symbol. See page X.7.

Typically installed with VHB tape and silicone.




1 Elevation - Sign Type C4  
C4.1 Scale: 3" = 1' - 0"

**Sign Type C4 - Area Identification Flag**


10.5" w x 10" h double-sided, painted and screened .125" thick aluminum panel, 1/2" corner radius, fastened to two (2) 1" x 1" x 1/8" brushed aluminum angles.

Colors: 1, 3, satin finish.


Note: ADA regulations do not allow use of text on this sign type. Sign must be mounted with a minimum clearance of 80" above finished floor to bottom of the sign. See page X.7.



2 Section - Sign Type C4  
C4.1 Full scale



1 Elevation - Sign Type C5  
C5.1 Scale: 1½" = 1' - 0"



**Sign Type C5 - Area Identification Overhead**

36" w x 8" h double-sided, painted and screened 1/2" thick aluminum (or Sintra - less durable) panel, 1/2" corner radius, fastened to two (2) 1" x 1" x 1/8" brushed aluminum angles mounted to ceiling.

Colors: 1, 3, satin finish.


Symbol: 4", color 1.

Text: 3" Arial Regular.

Note: ADA requires text on this sign type to be a minimum of 3" high. Sign must be mounted with a minimum clearance of 80" above finished floor to bottom of the sign. See page X.7.

Sign length can be adjusted to accommodate longer messages if needed.

2 Section - Sign Type C5  
C5.1 Half full scale



3" min.

# Concessions

1 Elevation - Sign Type C6  
C6.1 Scale: 3" = 1' - 0"

**Sign Type C6 - Area Identification Letters**

3" h minimum precision cut letters. 1/4" thick painted or brushed aluminum.

**Color:** varies to match building architecture or site color theme.

**Text:** Arial Regular, size varies with location.



1 Elevation - Sign Type C7  
C7.1 Scale: 3" - 1' - 0"

**Sign Type C7 - Parking Area Identification**


12"w x 18" h painted .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, just single color back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: vary with location, satin finish.

Text: Arial Bold.



1 Layouts - Sign Type C7  
C7.2 Scale: 1½" - 1' - 0"



1 Elevation - Sign Type C8  
C8.1 Scale: 1" = 1' - 0"

**Sign Type C8 - Area Identification Symbol**

36" w x 41" h, 1/8" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall with tamper resistant hardware and/or adhesive.

Panel colors: 1 and 3, satin finish.

Text: Arial Bold, 2.5" cap. ht.




1 Elevation - Sign Type C9  
C9.1

**Sign Type C9 - Small Area Identification Symbol**


18" w x 12" h, 1/8" thick aluminum panel 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall with tamper resistant hardware and/or adhesive.

Panel colors: 1 and 3, satin finish.

Text: Arial Bold, 2.5" cap. ht.



1 Elevation - Sign Type D1  
D1.1



2 Post Detail - Sign Type D1  
D1.1 Full scale

Optional directional strips.  
2 3/4" x 12" aluminum panels  
1/8" thick.

**Sign Type D1 - Trailhead Identification (Small)**

12" w x 18" h, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to two (2) 2" x 2" galvanized steel utility posts with tamper-resistant hardware.

Panel colors: 1, 3, satin finish.


Post Height: 66".

Directional Panels: 2.75" h x 12" directional panels can be added if needed. Match colors and specifications of main sign panel. Typically installed with VHB tape or adhesive.

Text: Arial Bold, colors 1 and 3.





1 Layout - Sign Type D1  
 D1.2 Scale: 3" = 1' - 0"



2 Layout - Sign Type D1  
 D1.2 Scale: 3" = 1' - 0"



3 Layout - Sign Type D1 with Single Line Header  
 D1.2 Scale: 3" = 1' - 0"



2 Post Detail - Sign Type D3  
D3.1 Half full scale



2 Layout - D2 Two Line Header  
D2.2

1 Elevation - Sign Type D2  
D2.1

**Sign Type D2 - Trailhead Identification w/Map**

20"w x 30" h, 1/8" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to two (2) 3" x 3" x 3/16" galvanized steel angle post with tamper-resistant hardware.


Panel colors: 1, 3, satin finish.

Post Height: 72".

Directional Panels: 20"w x 2.75" h directional panels can be added if needed. Match colors and specifications of main sign panel. Typically installed with VHB tape or adhesive.

Symbols: 2.5", colors 1 and 10.


Text: Arial Bold, colors 1 and 3.




3 Layout - Sign Type D2  
D2.3 Horizontal Map



4 Layout - Sign Type D2  
D2.4 Vertical Map



**1** Elevation - Sign Type E1  
**E1.1** Scale: 1" = 1' - 0"



**2** Post Detail - Sign Type E1  
**E1.1**

Optional directional strips.  
 2 3/4" x 12" aluminum panels  
 1/8" thick.

**Sign Type E1 - Field Identification**

12" w x 18" h, 1/8" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to two (2) 2" x 2" x 3/16" galvanized steel angle post with tamper-resistant hardware.

Panel colors: 1, 3, satin finish.

Post Height: 66".

Directional Panels: 2.75" h x 12" directional panels can be added if needed. Match colors and specifications of main sign panel. Typically installed with VHB tape or adhesive.



**NOTE: Synthetic and grass fields have different rules.**


**1** Layout - Sign Type E1 One Line Header (Grass Field)  
**E1.2** Scale: 3" = 1' - 0"



**NOTE: A two line header requires a layout change for this sign type. The white header is extended 1" from the single line version.**

**Synthetic and grass fields have different rules.**

**1** Layout - Type E1 Two Line Header (Synthetic Field)  
**E1.3** Scale: 3" = 1' - 0"



1 Elevation - Sign Type E2  
E2.1 Scale: 3" - 1' - 0"

**Sign Type E2 - Court Identification (Tennis)**

18.5" round, painted .080" thick aluminum panel, matte vinyl both sides with 3M Vandal Resist, fastened to fence with tamper-resistant hardware.

Panel colors: 1, 2, 12, satin finish.

Number Text: 9" cap. ht., Arial Bold, color 2.



1 Elevation - Sign Type E3  
E3.1 Scale: 3" - 1' - 0"

**Sign Type E3 - Field Identification (Ball)**

18.5" round, painted .080" thick aluminum panelmatte vinyl both sides with 3M Vandal Resist, fastened to fence with tamper-resistant hardware.

Panel colors: 1, 2, 10 satin finish.

Number Text: 10" cap. ht., Arial Bold, color 2.



1 Elevation - Sign Type E4  
E4.1 Scale: 3" - 1' - 0"

**Sign Type E4 - Field Identification (Multi-sport)**

18.5" round, painted .080" thick aluminum panel matte vinyl both sides with 3M Vandal Resist, fastened to fence with tamper-resistant hardware.

Panel colors: 1, 2, 3, satin finish.

Number Text: 6" cap. ht., Arial Bold, color 2.




1 Elevation - Sign Type F1  
 F1.1 Scale: 3" - 1' - 0"

**Sign Type F1 - Field Use By Permit**

12" x 18" h painted .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold and Regular, colors 1, 3.



**1** Elevation - Sign Type F2  
F2.1 Scale: 3" - 1' - 0"

**Sign Type F2 - Field Maintenance**

18" w x 12"h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to fence with tamper-resistant hardware.

Panel colors: 1, 3, satin finish.

Text: Arial Bold and Regular, color 1.



1 Elevation - Sign Type F3  
F3.1




Sign Type F3 - Do Not Feed Wildlife  
Do not Remove Waterfowl, No Dumping

12"w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, 10, satin finish.

Text: Arial Bold, colors 1, 3.



1 Elevation - Sign Type F4  
 F4.1 Scale: 3" - 1' - 0"

**Sign Type F4 - Restroom Location**

12"w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold, colors 1, 3.



1 Elevation - Sign Type F5  
 F5.1 Scale: 3" - 1' - 0"

**Sign Type F5 - Restroom Location w/Map**

12"w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold, colors 1, 3.

Map: 7.5"x10" digital print applied directly to panel surface or screened on to sign panel. Orient map to viewer and include north arrow.




1 Elevation - Sign Type F6  
F5.1

**Sign Type F6 - No Smoking**

12" w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold, colors 1, 3.





1 Elevation - Sign Type F7  
F5.1

**Sign Type F7 - Picnic Pavilion Sign**

12"w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold, colors 1, 3.



2 Post Detail - Sign Type H1  
H1.1

1 Elevation - Sign Type H1  
H1.1 Scale: 1" = 1' - 0"

Optional directional strips.  
2 3/4" x 12" aluminum panels  
1/8" thick.

**Sign Type H1 - Map**

20" w x 24" h, 1/8" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to two (2) 2" x 2" galvanized steel utility posts with tamper-resistant hardware.

Panel colors: 1, 3, satin finish.


Post Height: 72".

Map: 18" x 18" digital print laminated to 1/8" thick backer panel, mounted on sign with VHB tape or mechanical fasteners. Include logo, north arrow and orient map to viewer.

Directional Panels: 2.75" h x 20" directional panels can be added if needed. Match colors and specifications of main sign panel. Typically installed with VHB tape or adhesive.

Symbols: 2.5", colors 1 and 10.

Text: Arial Bold, colors 1 and 3.



1 Elevation - Sign Type K1  
K1.1 Scale: 1/2" - 1' - 0"

**Sign Type K1 - Kiosk**

Steel and wood construction provides space for information on both sides.



1 Photo - Sign Type K1  
K1.2 Not to scale

Typical kiosk used at several facilities.



2 Photo - Sign Type K1 (PCC)  
K1.2 Not to scale

The PCC facility uses a metal four-sided yellow and blue roofed kiosk.



1 Elevation - Sign Type L1  
 L1.1 Scale: 3" - 1' - 0"

**Sign Type L1 - Area Closed**

24"w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, color back side, fastened to post with tamper-resistant hardware.

**Colors:** Use appropriate background colors for specific conditions.

**Standard Sign Colors:** 1, 3, satin finish.

**Caution Sign Colors:** 1, 10, satin finish.

**Danger Sign Colors:** 1, 10, satin finish.

**Text:** Arial Bold, color 1.

**Temporary Messages:** Edge Print (or similar durable adhesive sticker) applied to sign panel.



1 Elevation - Sign Type L2  
 L2.1 Scale: 3" - 1' - 0"

**Sign Type L2 - Field Closed**

24"w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, color back side, fastened to post with tamper-resistant hardware.

Colors: Use appropriate background colors for specific conditions.

Standard Sign Colors: 1, 3, satin finish.

Caution Sign Colors: 1, 10, satin finish.

Danger Sign Colors: 1, 10, satin finish.

Text: Arial Bold, color 1.



1 Elevation - Sign Type L3  
 L3.1 Scale: 3" - 1' - 0"

**Sign Type L3 - Trail Closed**

24"w x 18" h painted .080" thick aluminum panel with screened text and logo, 1/2" corner radius, single-sided, fastened to post with tamper-resistant hardware.

**Colors:** Use appropriate background colors for specific conditions.

**Standard Sign Colors:** 1, 3, satin finish.

**Caution Sign Colors:** 1, 10, satin finish.

**Danger Sign Colors:** 1, 10, satin finish.


**Text:** Arial Bold, color 1.

**Temporary Messages:** Edge Print (or similar durable adhesive sticker) applied to sign panel.


## SEASONAL & EVENT SIGNS

Banners are typically used to inform the public about special or seasonal events.





1 Elevation - Sign Type R1  
R1.1 Scale: 1" - 1' - 0"



2 Post Detail- Sign Type R1  
R1.1


**Sign Type R1 - Park/Trail Rules**

12" w x 18" h, 1/8" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to one (1) 2" x 2" galvanized steel utility post with tamper-resistant hardware.

Panel color: 3, satin finish.


Text: Arial Bold, color 1 and 3.

Post Height: 6'.



Layout - Sign Type R1

**Type R1**  
Sign should be placed where a play structure or facility is located.




1 Elevation - Sign Type R2  
 R2.1 Scale: 3" - 1' - 0"

**Sign Type R2 - Disc Golf Rules**


12"w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall or 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, CMYK Map, satin finish.


Text: Arial Bold, colors 1, 3.



1 Elevation - Sign Type R3  
R3.1 Scale: 1" = 1' - 0"



2 Elevation - Sign Type R3 (Reverse)  
R3.1 Scale: 1" = 1' - 0"



3 Post Detail - Sign Type R3  
R3.1

**Sign Type R3 - Play Area Rules**

18"w x 24" h, 1/8" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist, fastened to two (2) 2" x 2" galvanized steel utility posts with tamper-resistant hardware.

Panel colors: 1, 3, satin finish.

Post Height: 66".

Text: Arial Bold and Regular, colors 1 and 3.

# Children's Play Area

**This play equipment is intended  
for children 5-12 years of age.  
Adult supervision is required.**


- Use play equipment as it is intended. Improper use may result in injury.
- Inspect play area before starting play. Immediately report any unsafe conditions on this play area to THPRD by calling 503/645-3539.
- Always use play equipment safely:
  - Never wear helmet, backpack, or clothing with strings while using play equipment.
  - No running, pushing or shoving.
  - Use slides in a safe, seated feet first position. Exit promptly to avoid collisions.
  - Never climb "up" slide.
  - Wear proper shoes when on play equipment.
  - Do not climb over or on the outside of any barrier wall.

**Park Patrol 971/246-0169**

**Violators subject to exclusion and/or fine.**



**1** Elevation - Sign Type R3  
**R3.2** Scale: 3" = 1' - 0"



1 Elevation - Sign Type R3 (Reverse Side)  
R3.3 Scale: 3" = 1' - 0"



1 Elevation - Sign Type R4  
 R4.1 Scale: 3" - 1' - 0"

**Sign Type R4 - Dog Park Rules**

12"w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold, Regular and Bold Narrow, colors 1, 3.




1 Elevation - Sign Type R5  
R5.1 Scale: 3" - 1' - 0"

**Sign Type R5 - Basketball Rules**

18" w x 24" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall or 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, 10, satin finish.

Text: Arial Bold and Regular, colors 1, 3.




1 Elevation - Sign Type R6  
 R6.1 Scale: 3" - 1' - 0"

**Sign Type R6 - Hockey Rules**

18" w x 24" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall or 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold and Regular, colors 1, 3.



1 Elevation - Sign Type R7  
 R7.1 Scale: 3" - 1' - 0"

**Sign Type R7 - Skate Park Rules**

24" h x 18", .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall or 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold and Regular, colors 1, 3.



1 Elevation - Sign Type R8  
 R8.1 Scale: 3" - 1' - 0"

**Sign Type R8 - Tennis Rules**

12"w x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall or 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, 10, satin finish.

Text: Arial Bold, colors 1, 3.




1 Elevation - Sign Type R9  
 R9.1 Scale: 3" - 1' - 0"

**Sign Type R9 - Synthetic Field Rules**

12"x 18" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall or 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold and Regular, colors 1, 3.



1 Elevation - Sign Type R10  
 R10.1 Scale: 3" - 1' - 0"

**Sign Type R10 - BMX Track Rules**

18"w x 24" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall or 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold and Regular, colors 1, 3.



1 Elevation - Sign Type R11  
R11.1

**Sign Type R11 - Community Garden Rules**

18"w x 24" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall, fence or 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold and Regular, colors 1, 3.

## STANDARD SAFETY SIGNS

Standard Warning and Safety Signs are provided in Appendix A at the end of this document.

### Warning and Safety Signs:

CAUTION – Unimproved stairs or trail

CAUTION - Trails boardwalks, and bridges may be slippery when wet or icy


CAUTION – Slippery when wet or icy

CAUTION – Watch for fly balls

DANGER – No trespassing steep slope

NOTICE – Employees handling chemicals...

NO PARKING – Reserved for Park Patrol





1 Elevation - Sign Type S1  
S1.1

**Sign Type S1 - Walk Bicycles**

18"w x 12" h, .080" thick aluminum, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel color: 1, 3, satin finish.

Text: Arial Bold, color 1.



2 Elevation - Sign Type S1  
S1.2

**Sign Type S1 - Walk Bicycles - Smaller**

12"w x 12" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel color: 1, 3, satin finish.

Text: Arial Bold, color 1.

## STANDARD TRAFFIC SIGNS

The following list are State and Federal standard traffic signs typically used at THPRD facilities:

Traffic Safety Signs per Traffic Safety Supply Company 503-235-8531 [www.tssco.com](http://www.tssco.com)

### All signs:

- 0.080 Aluminum
- High intensity reflective grade
- Clear vandal 6 mil. applied
- 2 inch tubing with 2¼ inch post sleeve

### Regulatory Signs:

GR-1 NO RIGHT TURN Symbol (or left) 24 X 24 and 24 X 18  
GR-1P NO RIGHT TURN plaque, (or left) 24 X 24 and 24 X 18  
GR-110 ONE WAY (w/right or left arrow) 18 X 24  
GR-154 SPEED LIMIT \_\_\_\_  
GR-158 Stop 18 inch and 24 inch

### Warning Signs:

GW-22 Bicycle Crossing Symbol  
GW-22P BIKE XING (plaque)  
GW-23 Pedestrian Crossing Symbol 18 X 18  
GW-23P PED XING (plaque)

### Parking and Misc. Signs:

GP-36 LOADING ZONE 30 MIN. LIMIT 12 X 18  
GP-45 NO PARKING ANY TIME 12 X 18  
GP-52 NO PARKING BETWEEN SIGNS 12 X 18  
GP-97 RESERVED PARKING 12 X 18  
GP-103 TOW AWAY ZONE 12 X 6  
GP-110 VISITOR PARKING 12 X 18  
OR20-6B ACCESSIBLE PARKING 12 x 18  
OR20-6D VAN ACCESSIBLE PARKING 12 X 21


### ADA Parking Signs:

OR20-6B ACCESSIBLE PARKING 12 x 18  
OR20-6D VAN ACCESSIBLE PARKING 12 X 21

### Misc.:


INCOMING TRAFFIC DOES NOT STOP

2 Post Detail - Sign Type T1  
T1.1



POST ENLARGEMENT 'A-A'  
SECTION

SCALE: 1" = 3"



Sign Type T1 - Trail Directional


2.75" w x 18" h, 1/8" thick, aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to one (1) 3.5" x 3.5" structural plastic lumber post, forest green. See page X.7.

Panel colors: 1, 3, satin finish.


Post Height: 42".

Text: Arial Bold, color 1.

1 Elevation - Sign Type T1  
T1.1



1  
T1.2 Layout - Sign Type T1  
Scale: 1" = 1' - 0"



1 Elevation - Sign Type T2  
T2.1 Scale: 1" = 1' - 0"



2 Layout - Sign Type T2  
T2.1 Half full scale

**Sign Type T2 - Trail Mile Marker**

5"w x 7" h, .080" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware.

Panel colors: 1, 3, satin finish.

Post Height: 42".

Text: Arial Bold, color 1.



1 Elevation - Sign Type T3  
 T3.1 Scale: 3" - 1' - 0"


**Sign Type T3 - Trail Connection**

12"w x 18" h, .080" thick aluminum panel 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Map: digital print on vinyl with UV protective film applied to sign surface. Orient map to viewer and indicate viewer location. Include north arrow.

Panel colors: 1, 3, satin finish.

Text: Arial Bold and Regular, colors 1, 3.



1 Elevation - Sign Type T4  
T4.1 Scale: 1" = 1' - 0"



2 Layout - Sign Type T4  
T4.1 Scale: 3" = 1' - 0"



**Sign Type T4 - Trail Crossing**

8" square, .080" thick aluminum panel, 1/2" radius corners, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to 2" square galvanized utility post with tamper-resistant hardware.

Panel colors: 1, 3, satin finish.

Post Height: 42".

Text: Arial Bold, color 1.



1 Elevation - Sign Type T5  
T5.1

**Sign Type T5 - Pedestrian Directional**


Two (2) 12" w x 18" h, 1/8" thick aluminum panels, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to one post with VHB tape and/or adhesive or use tamper resistant hardware. Panel has two rounded corners facing outside.

Panel color: 3, satin finish.

Text: 3/4" Arial Bold Narrow, color 1.

Post Height: 6'.

Note: In some cases only one panel may be needed. Typically two panels will be used.



1 Elevation - Sign Type T6  
 T6.1 Scale: 3" - 1' - 0"

**Sign Type T6 - Wall Directional**

18"w x 18"h, 1/8" thick aluminum panel, 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened with VHB tape to wall.

Panel color: 3, satin finish.

Text: Arial Bold, color 1.



1 Elevation - Sign Type T7  
T7.1 Scale: 1½" - 1' - 0"



2 Layout - Sign Type T7  
T7.1 Scale: 1½" - 1' - 0"

**Sign Type T7 - Parking Lot Directional**

24"w x 18" h, .080" thick aluminum panel 1/2" corner radius, matte vinyl both sides with 3M Vandal Resist. Digital print front side, green back side, fastened to wall or 2" square galvanized utility post with tamper-resistant hardware. See page X.9.

Panel colors: 1, 3, satin finish.

Text: Arial Bold, colors 1.



Hinge to change message from "OPEN" to "CLOSED" for winter season.



"Overflow Lot" on reverse side to be read when panel is in up position.

1 Layout - Sign Type T7  
T7.2 Scale: 1½" - 1' - 0"



1 Elevation - Sign Type T8  
 T8.1 Scale: 1" = 1' - 0"


**Sign Type T8 - Vehicle Directional**

45.5"w x 42" h, 3/8" thick aluminum panel, 1/2" corner radius, matte vinyl digital print both sides with 3M Vandal Resist, fastened to two 3.5" square structural plastic lumber posts.

Panel color: 3, satin finish.

Text: 3" and 1.5" cap. ht. applied vinyl, Arial Bold, color 1.

Lot ID: 4.75" applied vinyl circle, color varies per site and location. Colors shown: 5, 10, 12



2 Post Detail - Sign Type T8  
T8.1 Scale: 3" = 1' - 0"



1 Photo - Sign Type T9  
T9.0 Not to scale

Sign Type T9 - Vehicle A-board

during peak visitor hours and at THPRD events.


## UNIQUE & SPECIAL SIGNS

THPRD has a variety of facilities, some of which have unique characteristics that are reflected in their unique signs. Examples of these are the Jenkins Estate and Tualatin Hills Nature Park. Also included in this section are interpretive signs from Commonwealth Lake and the Tualatin Hills Nature Park.

### The Jenkins Estate



Carved wood sign outside the main entry road.



Routed wood sign at entry.



Routed wood directional signs.

## Tualatin Hills Nature Park



Galvanized steel and porcelain sign at entry drive.



Carved wood sign at park entrance.




Galvanized steel and porcelain trail signs.

Throughout the District plant identification signs may be used to inform visitors. Staff determines the type of sign and materials that best match the unique needs of the facility.

Interpretive Signage



Commonwealth Lake interpretive signs use porcelain panels that convey information about the park and educate visitors about the wildlife. Porcelain offers excellent photo and illustration reproduction with anti-graffiti properties. It is generally considered a very durable material option. However, it is expensive to fabricate and can be damaged with rocks or BB gun shots, resulting in a chipped surface that may rust over time.



Tualatin Nature Park porcelain and galvanized steel interpretive signs.

---

ABCDEFGHIJKLMNOPQRSTUVWXYZ  
abcdefghijklmnopqrstuvwxyz  
0123456789.!?

Typeface  
Arial Regular

ABCDEFGHIJKLMNOPQRSTUVWXYZ  
abcdefghijklmnopqrstuvwxyz  
0123456789.!?


Typeface  
Arial Narrow

**ABCDEFGHIJKLMNOPQRSTUVWXYZ**  
**abcdefghijklmnopqrstuvwxyz**  
**0123456789.!?**

Typeface  
Arial Bold

ABCDEFGHIJKLMNOPQRSTUVWXYZ  
abcdefghijklmnopqrstuvwxyz  
0123456789.!?

Typeface  
Arial Narrow Bold



Color 1  
Name: White  
Match: 3M White Vinyl



Color 8  
PANTONE DS 73-1 U  
CMYK 0-100-100-0  
RGB 237-28-36




Color 2  
Name: Black  
Match: 3M Black Vinyl



Color 9  
PANTONE DS 321-5 U  
CMYK 40-90-100-25  
RGB 129-57-34




Color 3  
Name: Sign Dark Green  
Match: Pantone 3435



Color 10  
Name: Red  
Match: 3M Vinyl Tomato Red




Color 4  
PANTONE DS 202-1 U  
CMYK 100-67-0-70  
RGB 0-27-77



Color 11  
Name: Tennis Ball Green  
Match: PMS 381



Color 5  
PANTONE DS 196-1 U  
CMYK 100-67-0-0  
RGB 0-94-173



Color 12  
Name: Yellow  
Match: PMS 109



Color 6  
PANTONE DS 284-1 U  
CMYK 56-16-100-3  
RGB 13-150-72



Color 7  
PANTONE DS 36-1 U  
CMYK 0-55-96-0  
RGB 246-139-40

Note: colors shown on this page are approximate. Match colors with the respective swatch book.



**THPRD Logo**

The THPRD logo as used on signs.

The logo uses six colors:

**DS202-1U - Dark Blue, color 4**

**DS196-1U - Med Blue, color 5**

**DS284-1U - Med Green, color 6**

**DS36-1U - Orange, color 7**

**DS73-1U - Red, color 8**

**DS321-5U - Brown, color 9**

# Activity Pictograms



### Regulatory Pictograms



No Alcohol



No Bicycles



No Fishing



No Open  
Fires



No Pets



No  
Skateboarding



No Smoking



No Swimming



Leashed Pets




Stay on  
Trail



Use Trash Can



Walk  
Bicycles



Walk on  
Boardwalk




No Pets  
on leash



No Trucks

**Arrows**




**Information**




**Access Symbol**




**Restroom Symbols**






Restroom signs must be installed at 60" to the center of the sign above the finished floor on the latch side of the door. Install signs on doors as a last resort (never on a door that swings out toward the viewer).

**1 Restroom Identification**  
Scale: 1/4" = 1' - 0"



Overhead signs require 3" min. text and must have a clearance of 80" min. to the bottom of the sign.


**2 Overhead Signs**  
Scale: 1/4" = 1' - 0"




Don't install signs within road right of way unless agreement with jurisdiction can be arranged.

Keep signs visible from trail, un-obscured by foliage and in a location that is safe for pedestrian and bicycle traffic.


**3 Trail Signs**  
Scale: 1/4" = 1' - 0"






**SIGN TYPE STANDARD SMALL - ELEVATION**  
**SINGLE OR DOUBLE SIGN**





**POST ENLARGEMENT 'A-A'**  
**SECTION**

SCALE: 1" = 3"



## **VANDAL FILM**

THPRD staff currently uses a film-type material to decrease damage to sign panels caused by tagging and graffiti. The film is applied to the surface of sign panels, typically on top of any message on the sign.

The product currently in use is:

**MADICO Window Film, 6 mil. multi-ply film.**

As new anti-graffiti technology becomes available THPRD may wish to review the benefits of new products.

---

## **CITY OF BEAVERTON AND WASHINGTON COUNTY SIGN CODES/STANDARDS**

District staff researched City of Beaverton and Washington County Development Codes/Standards for Signage and met with City and County planners to verify the proposed sign designs. All signs designed for the THPRD Signage Master Plan comply with both the City and the County codes. All information pertaining to the City of Beaverton and Washington County Development Codes/Standards for Signage is to be verified with the City or the County and the application for a sign permit and building permit, if required, is to be completed and submitted to the City or County prior to District's new or replacement signs being installed.

### **METRO REGIONAL SIGNAGE**

Metro will be taking the lead in developing regional system signage to be put in place in the near future. Metro is searching for a regional brand identity and is hoping to make a decision by June 2009 that would propel this project forward. This proposed signage system is likely to affect Tualatin Hills Park & Recreation District regional trails and possibly larger parks and facilities within the District. All other THPRD parks, trails and facilities would follow the THPRD 2009 Signage Master Plan.

### **THE INTERTWINE – REGIONAL TRAILS SIGNAGE GUIDELINES**

The Intertwine Regional Trail Signage Guidelines serves as a technical resource to guide parks and transportation agencies as they plan, design, and fabricate wayfinding signage along regional trails in the Portland-Vancouver metropolitan area. Metro and its partners developed the manual in response to requests from the public for better uniformity and consistency of signage along regional trails. Additional impetus came with the advent of The Intertwine brand and the opportunity to give the regional trail system a unifying identity.

The guidelines are intended to be followed when signing off-street regional trails and on-street bicycle and pedestrian facilities that serve as the primary routes connecting one trail segment to the next. The manual gives guidance for sign placement, messaging and content, color, size, and font. It should be used when signing new trails for the first time or when replacing or retrofitting signs along existing trails.

Since it is primarily local parks and transportation agencies that will implement the signs, Metro and its partners felt that guidelines were more appropriate than standards. The guidelines are designed to offer flexibility to agencies that already have trail sign standards in place while also providing solutions for certain conditions where existing standards may fall short. For example, these guidelines embrace the increasing ubiquity and popularity of Oregon's standard green bicycle directional sign and recommends its use along on-street bicycle connections, while acknowledging that the sign is not ideal for use along off-street trails since it is not intended for pedestrians and does not generate intrigue about The Intertwine.

With these guidelines, parks and transportation agencies can provide regional trail users an attractive, consistent sign system.

Guidelines can be found at: [http://library.oregonmetro.gov/files/intertwine\\_regional\\_trail\\_signage\\_guidelines.pdf](http://library.oregonmetro.gov/files/intertwine_regional_trail_signage_guidelines.pdf)

---

# **Appendix A**

## **Safety Sign Supplement**